



San Bernardino Subdivision Pathing Study

Draft Final Report

DB E.C.O. North America, Inc. | January 2022

Summary

Context

In 2019, mixed traffic operations caused large inefficiencies and the BNSF effectively ran a two-track freight operation

Continuing three-track mixed operations has little growth potential on the current corridor due to infrastructure and operating limitations.

The San Bernardino Subdivision is projected to support 2% freight growth and new passenger services over the next 20 years.

There is a long list of projects to support service growth, but their impact on operations and phasing is not clear.

Method

The San Bernardino Study applies a new market-place framework to prioritize capital projects by the capacity improvements that they deliver. The study used the framework to assess which projects, in which order would support the desired levels of service on the San Bernardino Subdivision. The market-place framework defines a standard train metric to measure corridor capacity through train paths.

Like gridlines on paper, the train paths visualize capacity supply to assess utilization and frame benefit and trade-off discussions. The method enables management to compare operating data against the capacity metric and understand capacity utilization.


Results

The BNSF has recommendations and phasing plans to transform the corridor from mixed-traffic to traffic-separated over a 10–15-year planning horizon.

1. Signal upgrades represent the most effective method to increase mainline throughput: a 5-minute headway reduction raises mainline capacity by 50%
2. Terminal and mainline interface upgrades at Hobart and Commerce facilities enable trains to land and be processed without blocking the mainline
3. Traffic flow separation through targeted mainline improvements at stations and passenger service harmonization
4. Freight trains stage at Lenwood when awaiting entry windows into the terminals at Hobart and Commerce

Context

In 2019, mixed traffic operations caused large inefficiencies and the BNSF effectively ran a two-track freight operation.



Insights


2019 passenger operations required all three mainlines and consumed 50% of mainline capacity¹

Yard-lead movements & freight staging consumed 30% of capacity

95% of freight traffic operated on Mains 1 and 2

(1) BNSF advised that a 6-hour maintenance of way window should be assumed. Insight calculations are based on 216 available train slots


Continuing three-track mixed operations has little growth potential on the current corridor due to infrastructure and operating limitations



- 1. Terminal traffic blocks mainline flows**
- 2. Staging and junction movements block the mainline for extended periods of time**
- 3. Uncoordinated passenger schedules use track space inefficiently**
- 4. Signal system governs throughput on the mainline**


The San Bernardino Subdivision is projected to support 2% freight growth and new passenger services over the next 20 years

Projected train counts between CP Soto – Fullerton



Data sources: BNSF RTC train counts, HSR 2020 Draft Business Plan, LOSSAN 2020 Business Plan, Metrolink Service Expansion Schedules

There is a long list of projects to support service growth, but their impact on operations and phasing is not clear



How is rail capacity defined?

Train	Length		Weight		Power	
Infrastructure	Tracks		Grade		Junctions	
	Signals		Yards			
Operations	Number of train movements			Terminal operations		
	Freight cars transported per time period			Average speed of service		
	Tons of freight transported per time period			Stability of the operations		

We need to set a currency for capacity


(1) Based on HSR's 2020 Capital Cost Basis of Estimate Report

Method



A solid red horizontal bar.

The San Bernardino Study applies a new market-place framework to prioritize capital projects by the capacity improvements that they deliver. The market-place framework defines a standard train metric to measure corridor capacity through train paths. Like gridlines on paper, the train paths visualize capacity supply to assess utilization and frame benefit and trade-off discussions. The method enables management to compare operating data against the capacity metric and understand capacity utilization. The framework assesses which projects, in which order would support the desired levels of service on the San Bernardino Subdivision

The San Bernardino Study applies a new market-place framework to prioritize capital projects by the capacity improvements that they deliver



The market-place framework defines a standard train metric to measure corridor capacity through train paths




Capacity unit


(1) Tons per operative brake (2) Horsepower per ton



Like gridlines on paper, the train paths visualize capacity supply to assess utilization and frame benefit and trade-off discussions

Signal performance Mainline capabilities Mainline-yard interfaces



Supply







The framework assesses which projects, in which order would support the desired levels of service on the San Bernardino Subdivision

Illustrative



**Comprehensive service,
operations & infrastructure plans** 

Prioritized project list

Phase 1

- Signaling and interlocking improvement Part 1
- Station 1
- Yard staging improvements

Phase 2


- Station 2
- Signaling and interlocking improvement Part 2
- Yard upgrade Part 1
- Yard Connection track

Phase 3

- Yard west second lead track
- Yard East second lead track
- Construct 3rd track to Eastern limit

Phase 4

- Yard upgrade Part 2
- Intermodal yard
- Yard and mainline realignment
- 4th Main track




Service delivered	
●	Hourly passenger slot 35 Freight slots
●	30 min passenger slot 51 Freight slots
●	30 min passenger slot with peak overlay 65 Freight slots
●	15 min passenger slot 71 Freight slots


Results

BNSF can support freight traffic growth to 2040 (pre-HSR) by targeting four families of capacity enhancing projects


1. *Signal upgrades represent the most effective method to increase mainline throughput: a 5-minute headway reduction raises mainline capacity by 50%*
2. *Terminal and mainline interface upgrades at Hobart and Commerce facilities enable trains to land and be processed without blocking the mainline*
3. *Traffic flow separation through targeted mainline improvements at stations and passenger service harmonization*
4. *Freight trains stage at Lenwood when awaiting entry windows into the terminals at Hobart and Commerce*




Signal upgrades represent the most effective method to increase mainline throughput: a 5-minute headway reduction raises mainline capacity by 50%



Current signaling capabilities support 4 Trains paths per hour per track¹



Proposed signal upgrades could support 6 Trains paths per hour per track^{1 2}





(1) Measured for trains travelling in a uniform direction on a mainline track
Source: [Dick, C., et al. 2019.](#)


(2) Potential signalling solutions have been identified by the BNSF

Terminal and mainline interface upgrades at Hobart and Commerce facilities enable trains to land and be processed without blocking the mainline


Illustrative schematic of upgraded Hobart & CITCOM facilities




Traffic flow separation requires targeted mainline improvements at stations and passenger service harmonization




Staging trains at Lenwood when awaiting entry windows into the terminals at Hobart and Commerce releases 15 slots to the mainline (7 trains)



Current corridor conditions



In 2019, queuing trains consumed 15% of available mainline capacity




Staging trains at Lenwood reduces the risk of excess train queues in critical corridor segments


Used slot Blocked slots Occupied slot Slot released to the mainline

Recommended phasing plans

The recommended phasing plans are linked to desired 2022-2040 passenger counts while ensuring freight traffic movement and growth are protected



Train counts establish service needs




And determine operating and infrastructure requirements

Phasing plans allocate 2022-2040 passenger counts based on material received from Metrolink and LOSSAN

The San Bernardino Subdivision is projected to support 2% freight growth and new passenger services over the next 20 years



Projected train counts between CP Soto – Fullerton



Data sources: BNSF RTC train counts, HSR 2020 Draft Business Plan, LOSSAN 2020 Business Plan, Metrolink Service Expansion Schedules
DB E.C.O. North America, Inc. | January 2022




Service / Year	2022	2025	2030	2035	2040
IEOC	16	24	28	30	34
OC	26	32	34	40	46
91 Line	12	24	28	30	32
Pacific Surfliner	30	32	32	32	32
Sum	84	112	122	132	144




HSR sets an additional 85 trains per day

This Pathing Study delivers desired train counts by separating traffic through three stages using two operating templates and six infrastructure phasing plans




The 4-train passenger plan supports 2022-30 train counts through infrastructure phases 1-3 to separate traffic from 50% to 75%¹



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)

This 4-train plan template represents a catalogue of train slots that operators can select to inform the design of an operating plan.



Track assignment

Phase 1 infrastructure

Westbound

- Metrolink on Main 1
- Pacific Surfliner on Main 2

Eastbound

- Metrolink Main 3
- Pacific Surfliner on Main 3

Phase 2 infrastructure

Westbound

- Metrolink on Main 1
- Pacific Surfliner on Main 2

Eastbound

- Metrolink Main 3
- Pacific Surfliner on Main 3

Phase 3 infrastructure


Westbound

- Metrolink on Main 3
- Pacific Surfliner on Main 1

Eastbound

- Metrolink Main 3
- Pacific Surfliner on Main 2

To achieve 2022 train counts, Phase 1 infrastructure upgrades are required for 50% traffic separation¹ using the 4-train plan passenger operating structure



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)




Phase 1 upgrades focus on improving the corridor’s signaling system and on critical mainline-yard interfaces at CITCOM and Hobart

Train service output

Westbound:		Eastbound:	
IEOC	8 trains	IEOC	8 trains
OC	13 trains	OC	12 trains
91 Line	6 trains	91 Line	7 trains
Pacific Surfliner	15 trains	Pacific Surfliner	15 trains


Operating environment



Infrastructure projects

Project Name	Location (MP)	Initiative	Project Description	Project benefit
Commerce Station relocation	MP 148.3-148.7	Separating passenger and freight services	Relocate Commerce station from MP 148.3 to its new location (TBC) subject to engineering feedback on its feasibility of phasing. The station could remain decommissioned until the Commerce flyover is complete	Enables CITCOM to be remodeled with extended tracks. Enables future passenger and freight traffic separation
Hobart First Lead track	MP 147.3-149.8	Clearing mainline	Extend the Eastern Ave lead to 15,000 ft over the I-5 to CP Bandini. The bridge over the I-5 needs to be widened to support CITCOM tracks, Hobart leads and three mainlines.	Release mainline capacity through improvement of the freight landing procedure
CITCOM support tracks	MP 146.5-149.5	Unlocking facilities	Extend CITCOM support tracks to East Hobart and Bandini	15,000 ft support tracks enable freight trains to be processed without the need to occupy mainline tracks. CITCOM switching will become more efficient due to longer switching leads (~5,000 ft).
10-minute headway signal upgrade	Entire San Bernardino Subdivision	Clearing mainline	Upgrade the corridor’s signal system to support 10-minute headways	Trains not exceeding 8,500 ft, 100 TOB can run at 10-minute headways

To achieve 2025 train counts, phase 1-2 infrastructure upgrades are required for 50% traffic separation¹ using a 4-train plan passenger operating structure



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)

Phase 2 upgrades target freight terminal leads and staging enhancements to support traffic separation with a passenger option to add Placentia Station.

Train service output

Westbound:


IEOC	12 trains
OC	16 trains
91 Line	12 trains
Pacific Surfliner	16 trains

Eastbound:

IEOC	12 trains
OC	17 trains
91 Line	11 trains
Pacific Surfliner	16 trains

Operating environment


Consumed slots



Infrastructure projects

Project Name	Location (MP)	Initiative	Project Description	Project benefit
Commerce station siding	MP 149.2-150.2	Separating passenger and freight services	3,500 ft station siding does not require additional bridge space on I-5 or Rio Hondo river and could be located between them. The siding is long enough to allow passenger trains to pass at speed. The siding should have No.20 turnouts and signals.	Commerce station siding is part of the effort to provide meet locations for passenger trains to separate freight and passenger flows.
Hobart Second Lead track	MP 147.3-149.8	Clearing mainline	Extend the Industry lead to 15,000 ft over the I-5 to CP Bandini. The bridge over the I-5 needs to be widened to support both Hobart leads.	Release mainline capacity through improvement of the freight landing procedure. Due to frequency of traffic, Hobart needs to be able to arrive/depart two trains at a time. Two leads will prevent queueing on the mainlines and
La Mirada Lead Extension	MP 157.2-158.4	Unlocking facilities	La Mirada lead extension from Valley View Ave to Carmenita	Provide track connection for the freight local movements to access clients directly from La Mirada facility without the need to foul mainlines.
Lenwood Staging	BNSF Cajon Sub	Clearing mainline	Staging facility with four tracks close to Barstow	Provide entry windows for the freight trains into the terminals at Hobart, Commerce and ACTA
Placentia Station Platform	MP 43	Separating passenger and freight services	Additional station for Metrolink 91 services	Increased passenger coverage for Metrolink 91 services

To achieve 2030 train counts, phase 1-3 infrastructure upgrades are required for 75% traffic separation¹ using a 4-train plan passenger operating structure



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)

Phase 3 upgrades target station enhancements to enable increased passenger operations on Main 3 and targeted siding locations (that will become Main 4)

Train service output

Westbound:


IEOC	14 trains
OC	17 trains
91 Line	14 trains
Pacific Surfliner	16 trains

Eastbound:

IEOC	14 trains
OC	18 trains
91 Line	13 trains
Pacific Surfliner	16 trains

Operating environment


Consumed slots



Infrastructure projects


Project Name	Location (MP)	Initiative	Project Description	Project benefit
Buena Park Station Siding	MP 159.7-161.7			
Fullerton Station Siding	MP 164.6-165.6	Separating passenger and freight services	5000 ft sidings at the stations east and west of Fullerton	Separating passenger and freight services Provide passenger meet opportunities and raise capacity supply on M3 from 96 to 192 slots per day
West Corona Station Siding	MP 26.4-27.4	Separating passenger and freight services	5000 ft at Esperanza and Riverside	Provide passenger meet opportunities and raise capacity supply on M3 from 96 to 192 slots per day
Riverside La Sierra Station Siding	MP 18-19			
MP 33 Siding	MP 32.5-33.5	Separating passenger and freight services		
MP 12 Siding	MP 12-13	Separating passenger and freight services		
Buena Park, Fullerton, West Corona and Riverside platforms	--	Separating passenger and freight services	Decommission platform on M1	Discourage passenger flow to M1 and M2
Fullerton to Esperanza third track	MP 165.5-35.8	Separating passenger and freight services	Fullerton to Riverside Downtown investments (SCORE)	Provide passenger only third track between Fullerton and Riverside Downtown
Prado to Colton third track	MP 29.4-10.6	Separating passenger and freight services		
Esperanza siding	MP 30-35	Clearing mainline	Repurpose existing Esperanza to M1 track and recreate Esperanza north of M1 track	Provide additional staging opportunity between Lenwood and ACTA
Colton IMF leads	MP 3.2-6.1	Unlocking facilities	Double leads into Colton IMF for eastbound and westbound freight traffic.	

The 6-train passenger plan supports 2035-40 train counts through infrastructure phases 4-5 with 100% traffic separation¹



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)

This 6-train plan template represents a catalogue of trains slots that operators can select to inform the design of an operating plan.



Track assignment


Phase 4 infrastructure

Passenger operates on Main 3 all day
Freight operates on Main 1 and 2

Phase 5 infrastructure

Passenger operates on Main 3 all day
Freight operates on Main 1 and 2

To achieve 2035 train counts, phase 1-4 infrastructure upgrades are required for 100% traffic separation¹ using a 6-train plan passenger operating structure



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)




Phase 4 extends sections of fourth track to support higher train frequencies on Main 3 and Main 4

Train service output

Westbound:		Eastbound:	
IEOC	15 trains	IEOC	15 trains
OC	20 trains	OC	20 trains
91 Line	15 trains	91 Line	15 trains
Pacific Surfliner	16 trains	Pacific Surfliner	16 trains

Operating environment




Infrastructure projects

Project Name	Location (MP)	Initiative	Project Description	Project benefit
Fullerton to Coyote 4th track connection	MP 160.7-165.5	Separating passenger and freight services	4th track connection between Buena Park station siding and Fullerton station siding	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
Norwalk siding extension	MP 155-156.1	Separating passenger and freight services	4th track from Telegraph Rd to CP West Norwalk	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
CITCOM flyover	MP 149.2-150.2	Unlocking facilities	Passenger train flyover between I-5 and Rio Hondo river bridge	Provide freight train access into the CITCOM facility without fouling passenger flows on M3



To achieve 2040 train counts, phase 1-5 infrastructure upgrades are required for 100% traffic separation¹ using a 6-train plan passenger operating structure



(1) % passenger traffic operating on Main 3 (and sidings that will eventually become Main 4)

Phase 5 extends sections of fourth track to support higher train frequencies on Main 3 and Main 4

Train service output

Westbound:


IEOC	15 trains
OC	20 trains
91 Line	15 trains
Pacific Surfliner	16 trains

Eastbound:

IEOC	15 trains
OC	20 trains
91 Line	15 trains
Pacific Surfliner	16 trains

Operating environment

Consumed slots



Infrastructure projects

Project Name	Location (MP)	Initiative	Project Description	Project benefit
MP34 to La Sierra 4th track	MP 34-18	Separating passenger and freight services	4th track connection between West Corona and La Sierra stations	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
Riverside Siding Extension	MP 12-10.3	Separating passenger and freight services	4th track connection between MP 12 and Riverside Downtown station	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day

Appendix

A solid red horizontal bar.

1. Capital project list
2. Capacity components
3. Illustrative Stringline charts
4. Infrastructure phasing schematics


Infrastructure project list (1/2)

Stage,	Passenger operating template	Train Count year	Project Name	Location (MP)	Initiative	Project Description	Project benefit
1	4-Train Plan	2022	Commerce Station relocation	MP 148.3-148.7	Separating passenger and freight services	Relocate Commerce station from MP 148.3 to its new location (TBC) subject to engineering feedback on its feasibility of phasing. The station could remain decommissioned until the Commerce flyover is complete	Enables CITCOM to be remodelled with extended tracks. Enables passenger and freight traffic separation
			Hobart First Lead track	MP 147.3-149.8	Clearing mainline	Extend the Eastern Ave lead to 15,000 ft over the I-5 to CP Bandini. The bridge over the I-5 needs to be widened to support CITCOM tracks, Hobart leads and three mainlines.	Release mainline capacity through improvement of the freight landing procedure
			CITCOM support tracks	MP 146.5-149.5	Unlocking facilities	Extend CITCOM support tracks to East Hobart and Bandini	15,000 ft support tracks enable freight trains to be processed without the need to occupy mainline tracks. CITCOM switching will become more efficient due to longer switching leads (~5,000 ft).
			10-minute headway signal upgrade	Entire San Bernardino Subdivision	Clearing mainline	Upgrade the corridor's existing existing system to support 10-minute headways	Trains not exceeding 8,500 ft, 100 TOB can run at 10-minute headways
2	4-Train Plan	2025	Commerce station siding	MP 149.2-150.2	Separating passenger and freight services	3,500 ft station siding does not require additional bridge space on I-5 or Rio Hondo river and needs to be located between them. The siding is long enough to allow passenger trains to pass at speed. The siding needs to have No.20 turnouts and signals.	Commerce station siding is a part of the effort to provide meet locations for passenger trains to separate freight and passenger flows.
			Hobart Second Lead track	MP 147.3-149.8	Clearing mainline	Extend the Industry lead to 15,000 ft over the I-5 to CP Bandini. The bridge over the I-5 needs to be widened to support both Hobart leads.	Release mainline capacity through improvement of the freight landing procedure. Due to frequency of traffic, Hobart needs to be able to arrive/depart two trains at a time. Two leads will prevent queueing on the mainlines and
			La Mirada Lead Extension	MP 157.2-158.4	Unlocking facilities	La Mirada lead extension from Valley View Ave to Carmenita	Provide track connection for the freight local movements to access clients directly from La Mirada facility without the need to foul mainlines.
			Lenwood Staging	BNSF Cajon Sub	Clearing mainline	Staging facility with four tracks close to Barstow	Provide entry windows for the freight trains into the terminals at Hobart, Commerce and ACTA
			Placentia Station Platform	MP 43	Separating passenger and freight services	Additional station for Metrolink 91 services	Increased passenger coverage for Metrolink 91 services

Infrastructure project list (2/2)

Phase	Passenger operating template	Train Count year	Project Name	Location (MP)	Initiative	Project Description	Project benefit
3	4-Train Plan	2030	Buena Park Station Siding	MP 159.7-161.7	Separating passenger and freight services	5000 ft sidings at the stations east and west of Fullerton	Separating passenger and freight services Provide passenger meet opportunities and raise capacity supply on M3 from 96 to 192 slots per day
			Fullerton Station Siding	MP 164.6-165.6			
			West Corona Station Siding	MP 26.4-27.4			
			Riverside La Sierra Station Siding	MP 18-19	Separating passenger and freight services	5000 ft at Esperanza and Riverside	Provide passenger meet opportunities and raise capacity supply on M3 from 96 to 192 slots per day
			MP 33 Siding	MP 32.5-33.5			
			MP 12 Siding	MP 12-13			
			Buena Park, Fullerton, West Corona and Riverside platforms	--	Separating passenger and freight services	Decommission platform on M1	Discourage passenger flow to M1 and M2
			Fullerton to Esperanza third track	MP 165.5-35.8	Separating passenger and freight services	Fullerton to Riverside Downtown investments (SCORE)	Provide passenger only third track between Fullerton and Riverside Downtown
			Prado to Colton third track	MP 29.4-10.6	Separating passenger and freight services		
4	6-Train Plan	2035	Esperanza siding	MP 30-35	Clearing mainline	Shift existing Esperanza staging track	Provide additional staging opportunity between Lenwood and ACTA
			Colton IMF leads	MP 3.2-6.1	Unlocking facilities	Double leads into Colton IMF for eastbound and westbound freight traffic.	
			Fullerton to Coyote 4th track connection	MP 160.7-165.5	Separating passenger and freight services	4th track connection between Buena Park station siding and Fullerton station siding	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
5	6-Train Plan	2040	Norwalk siding extension	MP 155-156.1	Separating passenger and freight services	4th track from Telegraph Rd to CP West Norwalk	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
			CITCOM flyover	MP 149.2-150.2	Unlocking facilities	Passenger train flyover between I-5 and Rio hondo river bridge	Provide freight train access into the CITCOM facility without fouling passenger flows on M3
			MP34 to La Sierra 4th track	MP 34-18	Separating passenger and freight services	4th track connection between West Corona and La Sierra stations	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day
			Riverside Siding Extension	MP 12-10.3	Separating passenger and freight services	4th track connection between MP 12 and Riverside Downtown station	Provide passenger meet opportunities and raise capacity supply on M3 from 144 to 288 slots per day

Explanation of capacity components



OS Data insights

Based on 2019 OS data, 15% of capacity is consumed by junction movements and track switches

Based on 2019 OS data, Freight consumes 1.4 slots on average for each movement in and out of the yards

Based on 2019 OS data, 15% of capacity is consumed by junction movements and track switches


Based on 2019 data, each freight train consumes on average 2 slots in total. Extra slots consumed embody the variability in freight operation.

Used slot Blocked slots Occupied slot



2022 Metrolink Schedule – San Bernardino Subdivision


4-Train Plan on Phase 1 infrastructure, 50% separation - Westbound passenger traffic on the M1 and M2 freight tracks



Disclaimer: These stringlines are based on prior Metrolink proposals rebased on to the passenger service templates. They were developed solely to inform capacity consumption calculations and should not be interpreted as final operating schedules.

2025 Metrolink Schedule – San Bernardino Subdivision


4-Train Plan on Phase 2 infrastructure, 50% separation - Westbound passenger traffic on the freight tracks






2030 Metrolink Schedule – San Bernardino Subdivision

4-Train Plan on Phase 3 infrastructure, 75% separation – Amtrak traffic on the freight tracks



2035 Metrolink Schedule – San Bernardino Subdivision


6-Train Plan on Phase 4 infrastructure, 100% separation of passenger and freight services




Disclaimer: These stringlines are based on prior Metrolink proposals rebased on to the passenger service templates. They were developed solely to inform capacity consumption calculations and should not be interpreted as final operating schedules.


2040 Metrolink Schedule – San Bernardino Subdivision









6-Train Plan on Phase 5 infrastructure, 100% separation of passenger and freight services





Disclaimer: These stringlines are based on prior Metrolink proposals rebased on to the passenger service templates. They were developed solely to inform capacity consumption calculations and should not be interpreted as final operating schedules.













<p>LEGEND</p> <div>  Track segment  Track segment included as reference  Proposed new track segment </div> <div>  Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)  Passenger platform with length (feet) </div> <div>  AREMA speed use (passenger/freight mph)  Passenger speed (mph)  Freight speed (mph) </div> <div>  Approximate mile marker  Control point with official milepost </div>										<p>Current Infrastructure</p>	<p>SAN BERNARDINO - SHORTWAY SUBDIVISIONS</p> <p>BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3])</p> <p>SCRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])</p>	<p>DATE: May. 11, 2021</p> <p>SHEET: 2</p>
---	--	--	--	--	--	--	--	--	--	-------------------------------	---	--




<p>LEGEND</p> <p>  Track segment  Track segment included as reference  Proposed new track segment </p> <p>  Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)  Passenger platform with length (feet) </p> <p>  AREMA speed used (passenger/freight mph)  Passenger speed (mph)  Freight speed (mph) </p> <p>  Approximate mile marker  Control point with official milepost </p>										<p>DATE: May. 11, 2021</p>
<p>SAN BERNARDINO - SHORTWAY SUBDIVISIONS</p> <p>BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3])</p> <p>SCRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])</p>										<p>SHEET: 3</p>




LEGEND												SAN BERNARDINO - SHORTWAY SUBDIVISIONS		DATE: May. 11, 2021	
	Track segment		Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)	45/40	AREMA speed use (passenger/freight mph)		20.0	Approximate mile marker		Control point with official milepost	Phase 1	BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3]) SCRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])		SHEET: 4	
	Track segment included as reference		Passenger platform with length (feet)	79	Passenger speed (mph)										
	Proposed new track segment		Passenger platform with length (feet)	79	Freight speed (mph)										





<p>LEGEND</p> <p>  Track segment  Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)  AREMA speed used (passenger/freight mph)  Approximate mile marker  Control point with official milepost </p> <p> Track segment included as reference Passenger platform with length (feet)  Passenger speed (mph)  Freight speed (mph) </p> <p> Proposed new track segment </p>										<p>Phase 2</p>	<p>SAN BERNARDINO - SHORTWAY SUBDIVISIONS</p> <p>BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3])</p> <p>SCRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])</p>	<p>DATE: May. 11, 2021</p> <p>SHEET: 5</p>
---	--	--	--	--	--	--	--	--	--	----------------	---	--





LEGEND																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
--------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--























LEGEND										Phase 5	SAN BERNARDINO - SHORTWAY SUBDIVISIONS BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3]) SCRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])	DATE:	
	Track segment		Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)	45/40	AREMA speed use (passenger/freight mph)		20.0	Approximate mile marker				Control point with official milepost	May. 11, 2021
	Track segment included as reference			79	Passenger speed (mph)								SHEET:
	Proposed new track segment		985'	79	Freight speed (mph)							12	





LEGEND								SAN BERNARDINO - SHORTWAY SUBDIVISIONS	DATE: May. 11, 2021
	Track segment		Maximum turnout or crossover speed (60 mph passenger / 40 mph freight)		AREMA speed use (passenger/freight mph) 45/40		Approximate mile marker	Full Build (HSR)	BNSF SAN BERNARDINO SUBDIVISION (CP Soto [MP 144.4] - CP San Bernardino [MP 0.3]) SCRRRA SHORTWAY SUBDIVISION (CP Rana [MP 2.2] - CP Vernon [MP 0.3])
	Track segment included as reference				Passenger speed (mph) 79				
	Proposed new track segment		Passenger platform with length (feet) 985'		Freight speed (mph) 79		Control point with official milepost CP Helen 10.5		
									14